



2160 - SPECIFICATION FOR REMOVAL OF FENCE

2160 - 1 DESCRIPTION

- 1.01 The work shall consist of the removal of fences and fabricated gates shown on the plans or designated by the Engineer.
- 1.02 Fabricated gates will not include texas gates.

2160 - 2 MATERIALS

2160 - 3 CONSTRUCTION

- 3.01 Fences shall not be removed until written instructions have been issued by the Engineer. Fences affecting the moving of power and telephone lines shall be removed within fourteen (14) days of receiving written instruction.
- 3.02 Wire shall be carefully removed from the posts. Useable wire shall be rolled in such a manner that it may be restrung. Fabricated gates shall be removed. Posts having a salvage value shall be pulled from the ground.
- 3.03 If posts and wire having a salvage value are damaged beyond use, the Contractor shall replace, at no direct expense to the Department, the damaged material with material of equivalent quality and quantity.
- 3.04 Useable material shall be salvaged and stored at sites shown on the plans or designated by the Engineer. Sites will be within the contract limits.
- 3.05 Non-useable materials shall not be disposed of without the consent of the landowner. Non-useable wooden posts, which the landowner does not wish to retain, shall be burned when burning is permitted. Non-useable wire, fabricated gates, or other non-combustible materials, which the landowner does not wish to retain, shall be disposed of within the contract limits as directed by the Engineer.

2160 - 4 MEASUREMENT

- 4.01 Removal of Fence will be measured in metres. The length of fence will include the length of fabricated gates.
- 4.02 Length will be determined from horizontal measurements.

2160 - 5 PAYMENT

- 5.01 Payment for REMOVAL OF FENCE will be at the contract unit price per metre. The unit price will be full compensation for removing and rolling wire, removing gates, pulling posts, hauling, storing useable materials, and disposing of non-useable materials.
- 5.02 Payment for removal of texas gates will be on an Extra Work Basis.